

# Bid 19-47, Addendum 1



**Date:** Monday October 07, 2019

**To:** All Prospective Vendors

**From:** Adonis Bwashi – 479.575.8258 – [abwashi@fayetteville-ar.gov](mailto:abwashi@fayetteville-ar.gov)

**RE:** Bid 19-47, Heavy Duty Trucks

CITY OF  
**FAYETTEVILLE**  
**ARKANSAS**

This addendum is hereby made a part of the contract documents to the same extent as though it were originally included therein. Bidders should indicate their receipt of same in the appropriate blank of the Bid Form. **BIDDERS SHOULD ACKNOWLEDGE THIS ADDENDUM ON THE DESIGNATED LOCATION ON THE BID FORM.**

## 1. Amendments on Specifications:

- The Description on Page 3 for Items 1 and 2 should be swapped:
  - Item #1: 1.5 Ton, Diesel, 4x4, CrewCab,9' Dump Body (installed)
  - Item #2: 1.5 Ton, Diesel, 4x4, Crew Cab,9'Utility Body (installed)
- On page 14 the description is also wrong: should be Item #1: 1.5 Ton, Diesel, 4x4, CrewCab,9' Dump Body (installed)
- Page 17, 3.14C – Will also except Electric over hydraulic, power up/power down
- Page 17 the description is also wrong: should be Item #2: 1.5 Ton, Diesel, 4x4, Crew Cab,9'Utility Body (installed)
- Page 22, 5.13A should say 4 compartments
- Page 25, 6.13A will accept 11'6" in length
- Page 25, 6.13B Drop down sides must fold down 180 degrees
- Page 25, 6.13C will accept 1,000-pound capacity over cab material rack
- Page 25, 6.13G add that if not using Tommy Gate G2 specifically, then it needs to meet:
  - 1600 lbs weight capacity or greater
  - Load area should be 87x35 inches
  - Taper of 6 inches
  - Steel construction

## 2. The following picture is clarification for Section 6.13, Line b. - 15-Inch hinged drop-down side stake racks.



The upper tool boxes are not required, but from the picture the sides can be lowered so that materials can be loaded.